BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Dasarahalli Division

D.T.S

NAME OF WORK:- De-setting and Re-settingof drain and re asphalting of roads to Chikkasandra Area in Ward No 12 Shettyhalli Sub Division					
S No	Item Name	Unit	Quantity	Rate In Figure in Rs	
				In Figures	in words
1	KSRRB 300-2. Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (PWD SR 2018-19 P.No: 143, I.No.: 19.2)	Cum	2471.49		
2	Lead and Lift charges for Exvated Earth including loading and unloading complete as per specifications.	Cum	2471.49		
3	KSRRB 300-58. Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. MORTH / Chapter 3 (PWD SR 2018-19 P.No: 147, I.No.: 19.64)	Sqm	7061.41		
4	KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406 (PWD SR 2018-19 P.No: 155, I.No.: 20.18)	Cum	1412.28		
5	KSRRB M500- 4 Providing and applying primer coat for surfaces of medium porosity like cement stabilized soil base @ 0.90kg/sqmt over prepared surface with S.S bitumen emulsion using bitumen tanker fitted with spray set (excluding cleaning of road surface) including cost of all material, labour, HOM of machineries complete as per specifications.. MORTH Chapter 501 of MORTH V revision (PWD SR 2018-19 P.No: 158, I.No.: 21.5)	Sqm	7061.41		

S No	Item Name	Unit	Quantity	Rate In Figure in	
				In Figures	in words
6	KSRRB 500-11. Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixd material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, HOM of machineries complete as per specifications. MORTH /Chapter 5 - using 100/120 TPH capacity H.M.P. with sensor paver Gr-1 (50 mm to 75mm) with 3.3 % VG-30 Bitumen (PWD SR 2018-19 P.No: 159, I.No.: 21.11.2)	Cum	353.07		
7	KSRRB M500- 4 Providing and applying primer coat for surfaces of medium porosity like cement stabilized soil base @ 0.90kg/sqmt over prepared surface with S.S bitumen emulsion using bitumen tanker fitted with spray set (excluding cleaning of road surface) including cost of all material, labour, HOM of machineries complete as per specifications.. MORTH Chapter 501 of MORTH V revision (PWD SR 2018-19 P.No: 158, I.No.: 21.5)	Sqm	7061.41		
8	KSRRB M500-18. Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 508 complete in all respects complete as per specifications. - using 100/120 TPH capacity H.M.P. with sensor paver Gr-II (25 mm to 30 mm) with 5 % VG-30 Bitumen (PWD SR 2018-19 P.No: 160, I.No.: 21.20.2)	Cum	176.54		

No	Item Name	Unit	Quantity	Rate In Figure in Rs	
				In Figures	in words
9	KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803 (PWD SR 2018-19 P.No: 182, I.No.: 24.5)	Sqm	389.84		

Number of corrections

Executive Engineer
Dasarahalli Division

DTS Approved

ಕಂಡಿಕೆ(—)ರಲ್ಲಿ ವಿವರಿಸಿರುವ ಅಂಶಗಳ ಬಗ್ಗೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು(E.E:)ರವರು
ದೃಢೀಕರಿಸಿಕೊಳ್ಳುವ ಷರತ್ತಿಗ ಒಳಪಡಿಸಿ ಡಿ.ಟಿ.ಎಸ್
ಅನುಮೋದಿಸಿದೆ.
ಕರದು ಟೆಂಡರ್ ಷೆಡ್ಯೂಲ್‌ನ್ನು ತಿದ್ದುಪಡಿ ಮಾಡದಂತೆ
ತಿದ್ದುಪಡಿ ಇಲ್ಲದೆ ಅನುಮೋದನೆ ನೀಡಲ್ಪಟ್ಟಿದೆ.
ತಿದ್ದುಪಡಿಗಳ ಒಟ್ಟು ಸಂಖ್ಯೆ:.....Nil.....
ರದ್ದುಗೊಳಿಸಿರುವ ಒಟ್ಟು ಐಟಂಗಳ ಸಂಖ್ಯೆ.....Nil.....

ಮುಖ್ಯ ಅಭಿಯಂತರರು (ದಾಸರಹಳ್ಳಿ)